

ADDENDUM No. 3

TO: ALL BIDDERS

FROM: CITY OF HIALEAH

BID #: 2013/14-9500-00-018

RE: HIALEAH ROWTP – Access Road Improvements NW 154th Street and NW 102nd Avenue

DATE: JUNE 27, 2014

The original contract documents for the entitled: **HIALEAH ROWTP – Access Road Improvements NW 154th Street and NW 102nd Avenue** needs to be amended as noted in this Addendum No. 3.

This Addendum No. 3 consists of 1 typed page, 1 attachment, and 1 addendum receipt form (ARF). All other items and conditions of the original Contract Documents shall remain unchanged. This Addendum shall become a part of the Contract Documents.

Approved for issue:  Date: June 27, 2014
Angel Ayala – Acting Purchasing Director

ACKNOWLEDGMENT

Receipt of this Addendum No. 3 shall be acknowledged in the space provided on the ADDENDUM RECEIPT form – ARF (Copy attached) now a part of the Contract Documents to be faxed immediately to the City of Hialeah Purchasing Division (305) 883-5871 and submitted with sealed bids.

Milian, Swain & Associates, Inc. (MSA) has reviewed the RAI's received from the bidders. See MSA responses as follow:

1. The plans call for "Existing FPL manhole ring and cover to be adjusted to proposed elevation." Who will be responsible for such adjustment? Normally this is FPL responsibility. Please clarify.

Existing FPL manholes rings and covers to be adjusted to propose elevation need to be done and considered on contractor bid.

2. Per visual inspection it seems to be a large amount of trash and debris on site within the right of way of the proposed roads. Under which pay item will the city compensate the contractor for the removal and disposal of it, or will the contractor allowed to push it aside? Please clarify.

Any existing trash and debris within the project limits should be removed and legally disposed off site by the contractor as part of item clearing and grubbing.

3. In our opinion, the quantity of Embankment must increase on the same quantity of Additional Excavation (2,635 CY).

Please see the bid form including the revised quantities for the bid items.

4. The Drawings shows 1" for Structural Course and 1" for Friction Course, why the quantities in TN are different?

Please see the bid form including the revised quantities for the bid items.

CITY OF HIALEAH

HIALEAH ROWTP – Access Road Improvements NW 154th Street and NW 102nd Avenue

BID #2013/14-9500-00-018

ADDENDUM No. 3

CONTRACTOR'S NAME _____

ADDRESS _____

PHONE NO. _____

CONTACT NAME _____ SIGNATURE _____

THE BIDDER ACKNOWLEDGES RECEIPT OF THE FOLLOWING ADDENDUM BY SIGNING AND DATING BELOW:
(Copy of this form must be faxed immediately to the City of Hialeah at (305) 883-5871).

ADDENDUM

SIGNATURE

DATE

3

ARF

**Hialeah R.O Water Treatment Plant
ACCESS ROAD IMPROVEMENTS (N.W 154th ST and N.W 102nd Ave)**

BID FORM

Rev: 6/25/14

City Bid Project Number:

Bid Opening Date:

Prepared by:

Date:

| BID ITEMS | | | | BID PROPOSAL | |
|---------------------------------------|--|----------------|------|-------------------|-------|
| Item | Description | Estimated Qty. | Unit | Unit Price | Total |
| A EARTHWORK | | | | | |
| 1. | CLEARING AND GRUBBING | 12,42 | AC | | |
| 2. | EXCAVATION | 32,788 | CY | | |
| 3. | ADDITIONAL SUBSOIL EXCAVATION (BETWEEN SPTS B-8 TO B-9 AVG 4') (SPTS B-10 TO B-11 AVG 1.5') ALONG N.W. 102ND | 2,635 | CY | | |
| 4. | EMBANKMENT | 55,180 | CY | | |
| 5. | EROSION CONTROL (SILT FENCE) | 18,000 | LF | | |
| | | | | TOTAL (A): | |
| B PAVING, GRADING AND DRAINAGE | | | | | |
| 1. | TYPE "B" STABILIZATION | 23,400 | SY | | |
| 2. | LIMEROCK BASE (8") | 23,400 | SY | | |
| 3. | TYPE "S-1" STRUCTURAL COURSE | 1,115 | TN | | |
| 4. | FRICTION COURSE | 1,115 | TN | | |
| 5. | DRAINAGE INLETS 60" Ø | 14 | E.A. | | |
| 6. | DRAINAGE INLETS 42" Ø | 22 | E.A. | | |
| 7. | DRAINAGE INLETS 36" Ø | 9 | E.A. | | |
| 8. | EXFILTRATION DRAIN (24") | 3,632 | LF | | |
| 9. | SOLID 18" PIPE | 4,149 | LF | | |
| 10. | SOLID 24" PIPE | 104 | LF | | |
| 11. | SOD (PENSACOLA BAHIA) | 30,735 | SY | | |
| | | | | TOTAL (B): | |
| C PAVING, MARKING AND SIGNAGE | | | | | |
| 1. | ROADSIDE SIGN POST AND STRAPS | 35 | AS | | |
| 2. | REFLECTIVE PAVEMENT MARKER (BI-DIRECTIONAL) | 180 | E.A. | | |
| 3. | REFLECTIVE PAVEMENT MARKER (AMBER/AMBER) | 76 | E.A. | | |
| 4. | SKIP 6" 10'X30' STRIPE, WHITE THERMOPLASTIC | 8,100 | LF | | |
| 5. | SOLID 6" DOUBLE YELLOW, THERMOPLASTIC | 610 | LF | | |
| 6. | SOLID 24" WHITE, THERMOPLASTIC | 50 | LF | | |
| | | | | TOTAL (C): | |
| D. SITE LIGHTING | | | | | |
| E. CONTINGENCIES | | | | | |
| TOTAL (A+B+C+D+E): | | | | | |

Contract prices for the various work items are intended to establish a total price for completing the project in its entirety. Payment for any item not listed in the Bid Form but shown in the plans shall be included in the proposal.